

THE 100 MYR STAR FORMATION HISTORY OF NGC 5471
FROM CLUSTER AND RESOLVED STELLAR PHOTOMETRYRUBÉN GARCÍA-BENITO^{1,2}, ENRIQUE PÉREZ³, ÁNGELES I. DÍAZ², JESÚS MAÍZ APELLÁNIZ^{3,4}, AND MIGUEL CERVIÑO³*Accepted by AJ*

ABSTRACT

We show that star formation in the giant HII region NGC 5471 has been ongoing during the past 100 Myr. Using HST/WFPC2 F547M and F675W, ground based JHKs, and GALEX FUV and NUV images, we have conducted a photometric study of the star formation history in the massive giant extragalactic HII region NGC 5471 in M101. We perform a photometric study of the colour-magnitude diagram (CMD) of the resolved stars, and an integrated analysis of the main individual star forming clusters and of NGC 5471 as a whole. The integrated UV-optical-nIR photometry for the whole region provides two different reference ages, 8 Myr and 60 Myr, revealing a complex star formation history, clearly confirmed by the CMD resolved stellar photometry analysis. The spatial distribution of the stars shows that the star formation in NGC 5471 has proceeded along the whole region during, at least, the last 100 Myr. The current ionizing clusters are enclosed within a large bubble, which is likely to have been produced by the stars that formed in a major event ~ 20 Myr ago.

Subject headings: HII Region, GEHR, star formation history, CMD

1. INTRODUCTION

Giant Extragalactic HII Regions (GEHRs) are important star formation tracers in the chemical evolution of galaxies and can be used as standard candles to estimate cosmological distances, thus they have been intensively studied. Equally important, they are the best indicators of the conditions that lead to massive star formation. These objects are very luminous H α emitters. Their H α luminosities, in the range $10^{39} - 10^{41}$ erg s⁻¹, imply large numbers of ionizing photons, $10^{51} - 10^{53}$ ph s⁻¹, an ionizing power equivalent to up to several thousands of O5V stars. Such a massive stellar concentration provides an excellent laboratory to study the modes of massive star formation.

The energy deposited in the interstellar medium in the form of stellar winds, supernova explosions and ultraviolet light produce complex stellar and gaseous spatial distributions which change rapidly during the few Myr following the onset of the first massive star generation. Although the massive young clusters that power the GEHRs are expected to form on a timescale shorter than 10 Myr, some studies in regions such as 30 Doradus in the LMC reveal that their stars may not be coeval (Walborn et al. 1999). The first population formed in the central regions may have induced star formation in the periphery through the action of UV radiation and stellar winds that compress the surrounding molecular clouds. Therefore, the study of the interrelation between stars, gas and dust components is highly relevant to understand the nature of these regions.

30 Doradus in the Large Magellanic Cloud (LMC) and

NGC 604 in M33 are the two largest GEHRs in the Local Group and they have been the subject of very detailed analyses. Both are dominated by very young (2-4 Myr) ionizing stellar populations, but they present two rather different stellar distributions. While NGC 604 is an extended *Scaled OB Association* (SOBA) with ~ 200 O+WR massive stars surrounded by nebular filamentary structures, 30 Doradus is powered by a Super Star Cluster (SSC) – a much more compact core (Maíz Apellániz 2001) – and a halo, with different stellar populations ranging from 2 to 20 Myr (Walborn & Blades 1997). Both GEHRs include an ongoing star formation with young stars still embedded in their parent molecular cloud. The structural similarities and differences between these well-studied and spatially well-resolved Local Group GEHRs have made them obvious ideal laboratories in which to study massive star formation, but in order to extrapolate our knowledge to distant luminous unresolved starbursts it is critically necessary to go a step further and to analyze in detail the somewhat more distant GEHRs just outside the neighbourhood of the Local Group.

M101 (NGC 5457) is a giant spiral galaxy located at a distance of 7.2 Mpc (Stetson et al. 1998) yielding a linear scale of 34.9 pc/arcsec. This galaxy contains a large number of very luminous GEHRs, of which NGC 5471 ($\alpha_{2000} = 14^h04^m29^s$, $\delta_{2000} = +54^\circ23'48''$; $l = 101^\circ78'$, $b = +59^\circ63'$) is one of the outermost, at a galactocentric radius of about 25 kpc (see figure 1). The H α morphology of NGC 5471 shows multiple cores with surrounding nebular filaments, extending over a diameter of $\sim 17''$, or ~ 600 pc. Ground-based photometry shows five bright knots, designated by Skillman (1985) as components A, B, C, D and E. Component A is as luminous as 30 Doradus, while components B, C and E are comparable to NGC 604, the two prototypical spatially resolved mini-starbursts in the Local Group. Thus NGC 5471 is truly

¹ Kavli Institute of Astronomy and Astrophysics, Peking University, 100871, Beijing, China; luwen@pku.edu.cn

² Departamento de Física Teórica (C-XI), Facultad de Ciencias, Universidad Autónoma de Madrid, Ctra. Colmenar Viejo km 15.600, E-28049 Madrid, Spain; angeles.diaz@uam.es

³ Instituto de Astrofísica de Andalucía, CSIC, Aptdo. Correos 3004, E-18080 Granada, Spain; eperez@iaa.es, jmaiz@iaa, mcs@iaa.es

⁴ Ramón y Cajal Fellow




FIG. 1.— Large scale image of M101. The grayscale is the Digital Sky Survey image and the contour image is the H I from the VLA (Braun 1995). NGC 5471 is located in the outskirts of the galaxy, in an arm concentration of H I.

a giant star forming region.

All these features make of NGC 5471 an excellent candidate for the study of complex star formation, being close to the limit distance between the spatially well resolved Local Group GEHRs and the more distant unresolved starbursts, thus providing an intermediate step in our understanding of very massive star forming regions.

This paper is organized as follows. Section 2 describes the observations and data reduction. Section 3 presents the integrated analysis of both the individual large clusters and the whole of NGC 5471, and the photometry of the resolved stars. The results found in section 3 are elaborated and discussed in Section 4. Finally, the conclusions are summarized in Section 5.

2. OBSERVATIONS AND DATA REDUCTION

We have retrieved ultraviolet NUV and FUV images of M101 from the GALEX archive, as well as broad and narrow band optical images for NGC 5471 from the HST archive. Finally, we have obtained near infrared JHK images.

2.1. GALEX data

The *Galaxy Evolution Explorer* (GALEX) far-ultraviolet (FUV; $\lambda_{ref} = 1530 \text{ \AA}$, $\Delta\lambda = 400 \text{ \AA}$) and near-ultraviolet (NUV; $\lambda_{ref} = 2310 \text{ \AA}$, $\Delta\lambda = 1000 \text{ \AA}$) images of M101 were retrieved from the Nearby Galaxies Survey (NGS).

The GALEX instrument is described by Martin et al. (2005) and its on-orbit performance by Morrissey et al. (2005). GALEX FUV and NUV imaging was obtained with total exposure times of 1041 s in each band. The 1σ NUV (FUV) sensitivity limit of the GALEX images is 27.6 (27.5) AB mag arcsec $^{-2}$ for these data (Bianchi et al. 2005). At the distance of M101, the linear scale of 34.9 pc'' implies that the GALEX point spread function (PSF) of 4.6 arcsec translates to 160 pc; this is barely sufficient to resolve some of the structure in NGC 5471, and we will only use the GALEX data to study the integrated photometry.




FIG. 2.— HST WFPC2 images of NGC 5471 in continuum corrected nebular filters H α (F656N), [SII] (F673N), and emission line corrected continuum filters F547M and F675W'. The five knots from Skillman (1985) are marked in the H α image. An ellipse indicating the core of the region is drawn in the H α and F675W' images.

2.2. HST/WFPC2 Imaging

Hubble Space Telescope (HST) Wide Field Planetary Camera 2 (WFPC2) images of NGC 5471 were retrieved from the HST archive. The images were taken on 1997 November 1 through two emission-line filters: F656N (H α) and F673N ([S II]), and two continuum filters: F547M (Strömgren y) and F675W (WFPC2 R) (Heyer et al. 2004). Each camera images onto a Loral 800 \times 800 CCD which gives a plate scale of 0''.046 pixel $^{-1}$ for the PC camera and 0''.10 pixel $^{-1}$ for the three WF cameras, with a readout noise of $\sim 5 \text{ e}^-$ and a gain of $7 \text{ e}^-/\text{DN}$ for this observations. NGC 5471 is centered in the WF3 camera in all images. The scale of the WF CCDs at NGC 5471, for which we assume a distance modulus of $(m - M) = 29.3$ (Stetson et al. 1998), is 3.5 pc pixel $^{-1}$. Table 1 lists the details concerning the WFPC2 data.

The HST-pipeline WFPC2 images were subjected to the usual processing using the IRAF⁵ and STSDAS⁶ software packages, following the procedures outlined in the HST Data Handbook. We used the multiple exposures to correct for the incidence of cosmic rays as well as to eliminate hot pixels and other defects on the CCD. We finally co-added the images to produce deep mosaics.

Given the luminosity of NGC 5471, its H α and [SII] emission contributes significantly to the broad band (F675W) image. To eliminate the nebular contribution from the broad band and to produce continuum-free H α

⁵ IRAF is distributed by the National Optical Observatory, which is operated by the Association of Universities for Research in Astronomy, Inc., under cooperative agreement with the National Science Foundation.

⁶ Space Telescope Science Data Analysis System (STSDAS) is a product of the Space Telescope Science Institute, operated by AURA for NASA

TABLE 1
JOURNAL OF HST/WFPC2 OBSERVATIONS OF NGC 5471.

Filter	Band	Exposure (s)	Observation ID
F547M	Strömgren y	2 × 600	U4DN030DR, U4DN030ER
		2 × 100	U4DN030FR, U4DN030GR
		20	U4DN030HM
F675W	WFPC2 R	2 × 400	U4DN0308R, U4DN0309R
		2 × 50	U4DN030AR, U4DN030BR
		10	U4DN030CR
F656N	H α	180	U4DN0305R
		2 × 600	U4DN0306R, U4DN0307R
F673N	[S II]	3 × 700	U4DN0301R, U4DN0302R, U4DN0303R
		300	U4DN0304R

NOTE. — All images were obtained on 1997 November 1 for the cycle 6 program GO-6928, with You-Hua Chu as PI. The object of study is centered in the WF3 camera.

and [SII] emission line images, we followed the procedure described below. First we multiplied the images by the PHOTFLAM parameter obtained by *synphot* to convert from count rates to flux densities, and then divided them by their respective time exposure. From the SYNPHOT task in STSDAS we determined the filter widths, and multiplied the flux densities found by the corresponding filter widths in order to obtain fluxes. The correct filter widths are the filter rectangular width RECTW (Luridiana et al. 2003) defined as the width in Ångströms of a rectangle with the same total area as the total transmission curve and a height given by the peak in the curve. We then scaled the H α , [S II] and F675W images and performed an iterative subtraction to obtain a new, emission line free, broad band image (F675W').

Figure 2 shows the H α image. The five brightest components first noted by Skillman (1985) and designated as A, B, C, D and E, are distinctly observed in that figure. The presence of a supernova remnant (NGC 5471B) is clearly seen as an intense [SII] emission source in the B-component in the F673N image. Previous works have associated X-ray sources with supernova remnants (SNRs) in M101. Chen et al. (2002) conclude that the energetic SNR in NGC 5471B (first identified by Skillman 1985) was very likely produced by a hypernova, an explosion one or two orders of magnitude brighter than the canonical 10^{51} erg energy explosion associated with a normal SN, although this result has been questioned recently (Jenkins et al. 2004).

2.3. Near-infrared photometry

JHK_s photometry was performed on 2000 April 29, using the 3.58m TNG (*Telescopio Nazionale Galileo*) at the Observatorio del Roque de los Muchachos in La Palma. The camera used was ARNICA (*ARcetri Near Infrared CAmera*), with a CCD detector NICMOS 256×256 HgCdTe and gain of 19 e⁻/ADU. The spatial scale was 0''.35 pixel⁻¹ and the field of view 90×90 arcsec². The details of these observations are given in Table 2.

The flux calibration of the images has been done using 2MASS images of NGC 5471, retrieved from the 2MASS Extended Source Catalog. We first measured the integrated flux of the 2MASS images in a circle containing the region and then, we used that aperture centered in the same coordinates and covering the same area in

TABLE 2
JOURNAL OF TNG/ARNICA OBSERVATIONS OF NGC 5471

Band	Time (UT)	Duration (s)	air mass
J	04:09:00	1 × 60	1.38
H	01:03:08	3 × 15	1.11
K _s	21:59:29	10 × 5	1.31

the ARNICA images. We obtained the photometric constants comparing the calibrated 2MASS fluxes with those from ARNICA by means of the transformation equations of the two systems.

In order to compare the two sets of optical and NIR data, we aligned the HST and TNG images. We degraded the WFPC2 images to the spatial scale and seeing of the IR ones, then we identified several objects in both data sets and marked them with the IRAF *center* routine. Next, we aligned the images with the *geomap* and *geotran* routines, using the HST images as reference.

Figure 3 shows the images and contour plots of the infrared bands. The multiple knots present in these images are well identified with those in Figure 2 in the F547M and F673W' filters.

3. RESULTS

3.1. Resolved Stellar Photometry

3.1.1. WFPC2 Photometry

The stellar photometric analysis was performed with the *HSTphot* package (Dolphin 2000a). This package is specifically designed for use with HST WFPC2 images. It uses a library of Tiny Tim (Krist 1995) undersampled point-spread functions (PSFs) for different locations of the star on the camera and of the star within the pixel, to center the star and to find its magnitude, given in the flight system magnitude. It also contains several programs for general reduction procedures. The first step is to run the *mask* task to mask out the bad pixels and other image defects identified in the data quality images. The sky computation is made by *getsky*, which takes all pixels in an annulus around each pixel, determines the




FIG. 3.— JHK_s grayscale images and contour plots. The isophotes range from 20 up to 100 per cent of the peak value of the image. An ellipse indicating the core of the region is drawn in the H image.

sky value and calculates the sky background map. The next step is to run `crmask` for cosmic ray removal, which uses the sky file created by `getsky`. It has the capability of cleaning images that are not perfectly aligned, and it can handle images from different filters. To combine multiple images per filter and to produce a final deep image per filter, the `coadd` procedure was used. The final step requires the `hotpixels` procedure, which uses the result from `getsky` and tries to locate and remove all hot pixels. This is an important step, since hot pixels can create false detections and also, can throw off the PSF solutions.

The `hstphot` routine was run on the images in the F547M and F675W' bands. This task performs stellar PSF photometry on multiple images from different filters, including alignment and aperture corrections, as well as PSF modifications to correct for errors of geometric distortion via the Holtzman et al. (1995) distortion correction equations and the 34th row error, noted by Shaklan et al. (1995) (see also Anderson & King 1999), and correction for charge transfer inefficiency (Dolphin 2000). There are several parameters to use during the run of `hstphot`. We enabled the determination of the “local sky” (from now on, *nebular* case), because of the rapidly-varying background of NGC 5471, but we also used, in a different run, the usual (*stellar*) fit done by `getsky`. We made a cross-correlation between the *nebular* and *stellar* lists of stars in order to match them and find the sources detected using both types of sky determination. To have a better estimate of the sky for those

matched stars, we took as magnitude the mean of both measurements $m = (m_{\text{nebular}} + m_{\text{stellar}})/2$ and as error:

$$\sigma_m = \max \left(\sigma_{m_n}, \sigma_{m_s}, \frac{|m_n - m_s|}{2} \right)$$

The final list of stars is made up of: i) matched stars; ii) objects from the *stellar* list not included in the *matched* star list (best detected in less nebulous regions); and iii) stars from the *nebular* list with no companion in the *stellar* list.

We selected “good stars” from the `hstphot` output. Object types were classified as good star, possible unresolved binary, bad star, single-pixel cosmic ray or hot pixel, and extended object. Less than 10% of the stars were not classified as “good stars”. To ensure that we only have point-like sources, we also used the “sharpness” parameter and a measure of the quality of the fit (χ^2) to reject false star detections in regions with structured nebulosity or artifacts. The final number of stars detected in the WF3 chip with these parameters in both filters were 1261.

3.1.2. Selection Effects

Completeness— In order to face the study of the star formation history (SFH) of an object and simulate synthetic diagrams, it is compulsory to undertake a completeness analysis. A thorough description of the completeness analysis can be found in Stetson & Harris (1988) and Aparicio & Gallart (1995). We briefly describe below its basis and main steps.

Incompleteness is mainly due to two factors: overlapping of stellar profiles in crowded regions and background noise. These effects are more important for faint stars in dense stellar regions. Consequently, in a crowded cluster incompleteness will depend on apparent magnitude and spatial position. The best way to account for crowding effects is to add artificial stars to the images and to subject them to the same sample selection as for real stars. The number of injected stars must be sufficiently high as to provide acceptable statistical accuracy, but not so high as to change the level of crowding. To avoid overcrowding effects, no more than some 10% of the number of real stars should be added as artificial stars. These new artificial images (*synthetic frames*) are processed in the same way as the real ones, and the magnitudes of all the stars are obtained following the same criteria and using the same parameters. At this point, we will have three different tables: *i*) the first one containing magnitudes, positions and colors of the real stars (*real stars*); *ii*) the second one including all the data for the *injected stars*, which are known beforehand; *iii*) the third list containing the data from the *synthetic frames*.

The *synthetic table* is then cross correlated with the other two (*real + injected*), producing a new table (*completeness*) containing the stars matched from the artificial list. Therefore, in this final list we have the initial and recovered magnitudes and colors of the injected stars, as well as their coordinates. The table will also contain stars which have not been paired, and a flag indicating that they have been lost. The ratio between the number of simulated stars recovered and injected provides the estimate of the completeness factor for each magnitude bin.

A grid of artificial stars was generated on a 2-dimensional CMD and distributed according to the flux of the images with an artificial star routine provided by *HSTphot*. The parameters of the routine are the minimum and maximum of the measured color and magnitude. The magnitude steps used were multiple of 0.5, while color steps are by 0.25. We asked the routine to distribute artificial stars on the CMD in accordance with the number observed. Approximately 40,000 fake stars were added in each image (at different trials, in order to leave the crowding conditions unaltered) and were given random magnitudes and colors in the observed range. We estimated the completeness in two different regimes of crowding: inside the core of the region (inner ellipse in Figure 4) and in the rest of the image. For the core, the 50% completeness of the F547M filter luminosity function derived on the basis of the CMD data is reached at 24.8 magnitude, while for the F675W' filter is 24.3 mag. For the rest of the image, the 50% completeness of the F547M filter is reached at 25.2 magnitude, while for the F675W' filter is 24.7 mag.

Field star subtraction— Statistical decontamination has been widely used to accomplish the field star subtraction of CMDs. The idea is very simple: our region of study, NGC 5471, consists of the sum of the intrinsic population, IP, and the contaminating population, FS, and therefore our CMD shows both populations. The field star contribution can be estimated using the CMD of an




FIG. 4.— Continuum free $H\alpha$ image of NGC 5471. The circular aperture of $15''$ where the integrated photometry was performed to obtain the total flux is overplotted together with the inner ellipse defining the core of the region.

adjacent field FS' containing only foreground and background stars, assuming that it is statistically representative of FS. Accordingly, the FS contribution may be removed by comparing the local density of stars in the two diagrams (Bellazzini et al. 1999):

$$CMD(IP + FS) - CMD(FS') \sim CMD(IP)$$

As NGC 5471 is centered in the WF3, we assume that all of the stars in the other chips are field stars. This is not completely true because this GEHR is in the outskirts of an M101 arm, where a few traces of star formation activity can still be found. Nevertheless, they are easily detected and no more than 20 stars in the WF2 (the only chip used to determine the FS population) were found over the chip. The rest of the stars showed a homogeneous distribution and were considered a sample of field stars. A $CMD(IP+FS)$ was constructed for a region inside a circular aperture of $15''$ which includes the core+halo structure of the region.

To perform the statistical decontamination, we followed the procedure described by Mighell et al. (1996) and Bellazzini et al. (1999). For a given star in the $CMD(IP+FS)$ with coordinates $[m \pm \sigma_m; c \pm \sigma_c]$, we count how many stars (N_{IP+FS}) can be found within the ellipse of axes $[max(\sigma_m, 0.1); max(\sigma_c, 0.1)]$ in the original diagram. We also counted the number of stars ($N_{FS'}$) found in the field $CMD(FS')$ within the same ellipse centered at the same coordinates.

The probability P that a given star in the $CMD(IP + FS)$ is actually a member of NGC 5471 is defined as follows:

$$P = 1 - \min\left(\frac{\alpha N_{FS'}}{N_{IP+FS}}, 1.0\right)$$

where α is the ratio of the area of the $IP+FS$ field (a circular aperture of $15''$) to the area of the FS' field (in this case, the whole WF2 chip). We can determine the probable membership of this star by comparing P with




FIG. 5.— Decontamination of the NGC 5471 observed CMD [panel (a)] using the field stars CMD [panel (b)]. The decontaminated NGC 5471 CMD is shown in panel (c) (610 stars) while the CMD of the rejected stars is displayed in the panel (d) (73 stars).

an uniform random number $0 < P' < 1$; if $P' \leq P$ then the star is accepted as a member of NGC 5471, otherwise it is rejected and considered as a field star. Since this cleaning method is probabilistic in nature, a decontaminating trial represents only one out of an infinite number of different realizations of the cleaned CMD for NGC 5471.

Figure 5 shows the result of this process of decontamination for the CMD of NGC 5471. Panel (a) displays the CMD observed (with both intrinsic and field stars), panel (b) the field stars, panel (c) the decontaminated CMD of and panel (d) the CMD of the stars rejected. Table 3 shows the magnitudes of the first 20 stars of the resulting clean CMD of panel (c); the full table can be accessed in the electronic edition.

3.1.3. Isochrones

To study the CMD we use the isochrone set that corresponds to the grid by Girardi et al. (2002)⁷, covering the age range $6.60 < \log t < 10.25$ and mass range 0.15 to $100 M_{\odot}$, based on the $Z=0.004$ ($1/5 Z_{\odot}$) models (see end of section 3.2 for a discussion on the choice of the metallicity) from Girardi et al. (2000) and Bertelli et al. (1994) that include overshooting and a simple synthetic evolution of TP-AGB (Girardi and Bertelli 1998). Atmosphere models are from BaSeL 3.1 WLBC 99 corrected library (Westera et al. 2002) at the same metallicity as the isochrone set.

The procedure is as follows: (1) we obtained the magnitudes in the HST filters for all stellar models in the atmosphere grid. (2) For each point in the isochrone we obtained the stellar flux in each of the bands by a linear




FIG. 6.— Final CMD corrected for field star contamination, together with five isochrones from 4 to 70 Myr. The line across the bottom shows the completeness limit at the 50% level as derived from false star tests for the core (dashed line) and for the rest of the image (solid line). The right-hand side scale gives the absolute magnitudes corresponding to a distance of 7.2 Mpc.

interpolation in the $\log g - \log T_{\text{eff}}$ grid. (3) The final luminosity was obtained by multiplying by the square radius of the star. For $\log g - \log T_{\text{eff}}$ values not covered by the atmosphere grid, the boundary values have been used with a caution flag. In terms of the present work, these stars do not modify the results obtained.

In Figure 6 we show the final CMD (corrected for field star contamination). The 50% completeness limit is also plotted, and five isochrones from 4 to 70 Myr are shown in colour. The right hand side scale gives the absolute magnitude corresponding to a distance of 7.2 Mpc.

3.2. Cluster Photometry

We have derived the integrated magnitudes and colors in eleven different apertures covering the main components in the core of NGC 5471. The apertures were chosen and defined in the H-band image, maximizing the area in order to include the features of all images, since there were some small offsets in the position and intensity of the knots in the optical and infrared images respectively. Then, the same polygons were used for the J, K_s and HST images. Polygons were marked by using the IRAF task `polymark` and the integrated magnitudes were computed using the IRAF task `polyphot`. The integrated magnitudes of the HST images are given in the VEGAMAG system. The polygons defined are shown in Figure 7.

The integrated magnitudes and colors derived in each area were corrected for the Galactic foreground extinction toward M101 using the color excess $E(B-V) = 0.01$ (Schlegel et al. 1998), although its effect is negligible. The absorption coefficients for the 5 bands were derived assuming $R_V = A_V/E(B-V) = 3.1$, and using the A_{λ} curve from Cardelli et al. (1989). The uncertainty of the individual fluxes have been computed including the Poisson photon count error, the uncertainty on the

⁷ Available at <http://pleiadi.pd.astro.it/>

TABLE 3
STELLAR PHOTOMETRY

ID	X pixel	Y pixel	R.A. (J2000)	Decl. (J2000)	m_{F547M} (mag)	$m_{F675W'}$ (mag)	$m_{F547M} - m_{F675W'}$ (mag)
1	359.56	562.57	14:04:27.50	54:23:41.53	24.24 ± 0.07	23.45 ± 0.05	0.79 ± 0.09
2	324.75	512.37	14:04:27.56	54:23:47.59	24.57 ± 0.10	23.93 ± 0.07	0.65 ± 0.12
3	352.44	544.56	14:04:27.57	54:23:43.36	24.05 ± 0.07	23.95 ± 0.06	0.09 ± 0.09
4	332.62	514.12	14:04:27.61	54:23:46.96	24.59 ± 0.09	24.88 ± 0.19	-0.30 ± 0.21
5	378.56	569.56	14:04:27.62	54:23:39.79	24.04 ± 0.06	23.62 ± 0.06	0.42 ± 0.08
6	323.33	496.44	14:04:27.66	54:23:48.91	24.07 ± 0.06	24.13 ± 0.12	-0.06 ± 0.14
7	373.56	553.15	14:04:27.69	54:23:41.37	24.18 ± 0.07	23.24 ± 0.05	0.94 ± 0.09
8	293.29	455.69	14:04:27.69	54:23:53.94	23.62 ± 0.05	22.57 ± 0.03	1.05 ± 0.06
9	351.67	523.45	14:04:27.71	54:23:45.04	23.85 ± 0.07	23.87 ± 0.11	-0.02 ± 0.13
10	290.75	449.59	14:04:27.71	54:23:54.57	23.86 ± 0.06	23.02 ± 0.04	0.84 ± 0.07
11	368.80	540.45	14:04:27.74	54:23:42.65	23.14 ± 0.03	23.24 ± 0.04	-0.10 ± 0.05
12	346.68	513.49	14:04:27.74	54:23:46.12	25.26 ± 0.15	24.89 ± 0.17	0.38 ± 0.23
13	381.63	555.86	14:04:27.75	54:23:40.66	24.08 ± 0.07	24.18 ± 0.11	-0.10 ± 0.13
14	360.90	530.61	14:04:27.75	54:23:43.91	23.96 ± 0.06	24.09 ± 0.09	-0.14 ± 0.10
15	318.82	469.76	14:04:27.81	54:23:51.25	25.22 ± 0.15	25.04 ± 0.20	0.18 ± 0.26
16	312.47	461.48	14:04:27.81	54:23:52.29	23.20 ± 0.04	23.22 ± 0.04	-0.02 ± 0.05
17	291.51	435.95	14:04:27.81	54:23:55.57	25.38 ± 0.21	25.23 ± 0.19	0.16 ± 0.28
18	359.87	517.56	14:04:27.83	54:23:44.98	24.20 ± 0.09	24.26 ± 0.10	-0.06 ± 0.13
19	354.84	509.85	14:04:27.84	54:23:45.89	24.02 ± 0.06	23.67 ± 0.05	0.34 ± 0.08
20	319.56	460.53	14:04:27.88	54:23:51.91	24.45 ± 0.08	24.87 ± 0.20	-0.42 ± 0.22

NOTE. — Stellar photometry. Table 3 is published in its entirety in the electronic edition. A portion is shown here for guidance regarding its form and content.




FIG. 7.— Plot of the eleven polygons, limiting the different areas where the integrated magnitudes are computed. The numbers belong to our own definition while the A, B, C, D and E letters are the knots identified by Skillman (1985). The hypernova is located in knot 6.

background setting and the photometric calibration uncertainty. The results of the integrated photometry are shown in Table 4.

We have also measured the $H\alpha$ flux for each polygon. To measure the integrated $H\alpha$ flux of the whole region, we have decontaminated the F656N image from the broad band F675W contribution. We have then plotted the contour at 3σ from the sky (with isophotal flux $6.3 \times 10^{-15} \text{ erg cm}^{-2} \text{ s}^{-1} \text{ arcsec}^{-1}$) and found the circular aperture centered in the region that best fits that isophotal contour. The radius of this aperture is 15 arcsec from

the center (see Figure 4). The flux measured inside this circular aperture is $(3.65 \pm 0.17) \times 10^{-12} \text{ erg cm}^{-2} \text{ s}^{-1}$. We have used the PHOTFLAM value given by *synphot* and a value of RECTW of 28.3 \AA . Measured $H\alpha$ fluxes for each of the polygonal selections and the parameters derived from them are given in Table 5. The effective radius (R_{eff}) of a polygon is defined as the radius of a circular aperture of the same area.

Since GALEX images do not have the necessary resolution, we were not able to get the fluxes for each polygon. As in the case of the nebular flux, we measured the FUV and NUV fluxes inside $15''$ radii apertures centered in NGC 5471. We obtain a FUV flux of $(9.9 \pm 0.1) \times 10^{-14} \text{ erg cm}^{-2} \text{ s}^{-1} \text{ \AA}^{-1}$ (14.19 ± 0.05 AB magnitudes) and a NUV flux of $(4.5 \pm 0.1) \times 10^{-14} \text{ erg cm}^{-2} \text{ s}^{-1} \text{ \AA}^{-1}$ (14.24 ± 0.05 AB magnitudes).

In order to use these values in the analysis, we need to transform AB magnitudes to the VEGAMAG system. The transformation formula is (Maíz Apellániz 2007):

$$AB_p = (m_p - ZP_p) + AB_p(\text{Vega}) \quad (1)$$

where AB_p is the magnitude of the object in the AB system and filter passband p , m_p the magnitude of the object in filter p using Vega as reference spectral energy distribution (SED), ZP_p is the zero point of the p filter in the Vega system and $AB_p(\text{Vega})$ is the AB magnitude of Vega in filter p . This magnitude is given by:

$$AB_p(\text{Vega}) = -2.5 \log_{10} \left(\frac{\int P_p(\lambda) f_{\lambda, \text{Vega}}(\lambda) d\lambda}{\int P_p(\lambda) (c f_{\nu, AB} / \lambda) d\lambda} \right) \quad (2)$$

where $P_p(\lambda)$ is the dimensionless filter sensitivity function of filter p , $f_{\lambda, \text{Vega}}(\lambda)$ is the Vega spectrum and $f_{\nu, AB} = 3.63079 \times 10^{-20} \text{ erg s}^{-1} \text{ cm}^{-2} \text{ Hz}^{-1}$ is the reference spectral energy distribution of the AB system.

TABLE 4
INTEGRATED PHOTOMETRY

Aperture	J	H	K _s	m _{547M}	m _{675W}	m _{675W'}
N5471-1	16.43 ± 0.11	16.26 ± 0.12	16.03 ± 0.14	16.66 ± 0.06	15.56 ± 0.06	16.30 ± 0.06
N5471-2	16.90 ± 0.11	16.57 ± 0.12	16.48 ± 0.14	17.21 ± 0.06	16.30 ± 0.06	16.94 ± 0.06
N5471-3	17.35 ± 0.11	17.09 ± 0.12	17.12 ± 0.14	17.22 ± 0.06	16.84 ± 0.06	17.11 ± 0.06
N5471-4	17.52 ± 0.11	17.08 ± 0.12	16.99 ± 0.14	18.17 ± 0.06	17.07 ± 0.06	17.77 ± 0.06
N5471-5	17.83 ± 0.11	17.28 ± 0.12	17.27 ± 0.14	18.58 ± 0.06	17.59 ± 0.06	18.16 ± 0.06
N5471-6	17.34 ± 0.11	17.21 ± 0.12	17.00 ± 0.14	17.62 ± 0.06	16.41 ± 0.06	17.12 ± 0.06
N5471-7	16.98 ± 0.11	16.59 ± 0.12	16.47 ± 0.14	17.56 ± 0.06	16.49 ± 0.06	17.10 ± 0.06
N5471-8	17.89 ± 0.11	17.41 ± 0.12	17.39 ± 0.14	18.70 ± 0.06	17.68 ± 0.06	18.22 ± 0.06
N5471-9	19.15 ± 0.13	18.63 ± 0.13	18.63 ± 0.15	20.23 ± 0.06	18.71 ± 0.06	19.54 ± 0.06
N5471-10	18.14 ± 0.11	17.80 ± 0.12	17.57 ± 0.15	18.63 ± 0.06	17.45 ± 0.06	18.22 ± 0.06
N5471-11	18.55 ± 0.12	18.00 ± 0.12	18.11 ± 0.15	19.27 ± 0.06	18.40 ± 0.06	18.84 ± 0.06
NGC 5471	14.14 ± 0.10	13.84 ± 0.12	13.74 ± 0.14	14.67 ± 0.06	13.62 ± 0.06	14.27 ± 0.06

NOTE. — Integrated magnitudes and H α flux for the eleven regions of NGC 5471. Magnitudes from HST are given in the VEGAMAG system. Results for m_{675W'} column were measured from the emission line free F675W image. The last row belongs to the integrated magnitud of the whole region.

TABLE 5
NEBULAR PHOTOMETRY

Aperture	R _{eff} pc	F(H α) 10 ⁻¹³ erg s ⁻¹ cm ⁻²	L(H α) 10 ³⁹ erg s ⁻¹	Q(H ⁰) 10 ⁵¹ s ⁻¹	M HII 10 ⁴ M _⊙
NGC5471-1	61.1	6.63 ± 0.31	4.1	4.1	13.0
NGC5471-2	60.9	3.07 ± 0.14	1.9	1.9	6.1
NGC5471-3	47.0	0.93 ± 0.04	0.6	0.6	1.9
NGC5471-4	51.2	1.59 ± 0.07	1.0	1.0	3.2
NGC5471-5	46.0	0.79 ± 0.04	0.5	0.5	1.6
NGC5471-6	58.9	2.42 ± 0.11	1.5	1.5	4.8
NGC5471-7	63.1	2.34 ± 0.11	1.5	1.4	4.7
NGC5471-8	43.5	0.72 ± 0.03	0.5	0.4	1.4
NGC5471-9	34.0	0.38 ± 0.02	0.2	0.2	0.8
NGC5471-10	46.2	1.22 ± 0.06	0.8	0.8	2.4
NGC5471-11	53.6	0.31 ± 0.01	0.2	0.2	0.6
NGC 5471	525	36.5 ± 1.70	23	22	73

NOTE. — Integrated H α flux and derived parameters for the eleven regions of NGC 5471. R_{eff} is the effective radius of the polygon. The last row belongs to the integrated values of the whole region.

We have used FUV and NUV filter passbands to calculate the AB magnitudes of Vega by means of equation 2. As the zero points for GALEX are ZP = 0.000 in both bands, we have

$$m_{FUV} = AB_{FUV} - 2.073 \quad (3)$$

$$m_{NUV} = AB_{NUV} - 1.647 \quad (4)$$

Finally, the GALEX VEGAMAG magnitudes of NGC 5471 used below are m_{FUV} = 12.12 and m_{NUV} = 12.59.

Although a complete analysis of the stellar populations is better characterized by the CMD study, integrated photometry provides additional information from wavelengths where CMD studies are not feasible. However, the usual methodology to infer properties from clusters based on their integrated light is not trivial for low mass clusters and we need to be sure that the procedure is valid before the use of any analysis tool. The first trivial test is that cluster luminosity fulfills the bolometric assumptions implicit in the synthetic photometry (cluster luminosities larger than the *Lowest Luminosity Limit* (LLL), Cerviño & Luridiana 2004). This basically es-

tablishes when the cluster luminosity in a given wavelength/filter *may be* produced by just an individual star⁸. The mean luminosity of a cluster obtained by population synthesis models can be safely used when the cluster is brighter than 10 times the LLL, or 2.5 in magnitude units (Cerviño & Luridiana 2004).

The results of the LLL analysis are shown in figure 8, where the ages are just first order estimations when LLL and additional limitations in the analysis are not taken into account. The figure shows that, with the exception of a few clusters, most of the clusters do not fulfill the 10×LLL safety limit. Thus, formally, the analysis based on the mean values obtained from synthesis models should be considered as preliminary and used with a cautionary note, as some could be biased by contributions from individual stars.

With this limitation in mind and taking into account that the results could be reinterpreted we have ana-

⁸ The LLL just establishes this possibility, but it does not provide more information about whether it is really the case.




FIG. 8.— Lowest-luminosity limit for the optical and infrared filters used in the cluster photometry. Each cluster is located at the age resulting from the CHORIZOS analysis. The continuous line indicates the LLL and the dotted line the “safety” limit of $LLL+2.5$.

lyzed the integrated photometric measurements with the help of CHORIZOS⁹, a code written in IDL by Maíz Apellániz (2004). This code compares photometric data with model spectral energy distributions (SEDs), calculating the likelihood for the full parameter range specified, allowing for the identification of multiple solutions. CHORIZOS can handle SED families for stellar atmospheres and the mean SED obtained by synthesis models¹⁰ (Starburst99; Leitherer et al. 1999) and uses χ^2 minimization to find all models compatible with the observed data in a (2 intrinsic +2 extrinsic)-dimensional parameter space. It includes a wide list of filters for different systems and allows for published magnitudes to be used directly. For a set of objects with $M+1$ measured magnitudes (with independent uncertainties), derived M independent colors, and a set of N parameters with $M > N$, no strict solutions, but only approximate ones, can be found since the problem has more equations or sets of model parameters that produce a given color than model parameters. Hence, the code finds the N -volume of approximate solutions by using χ^2 minimization by the comparison with synthetic photometry. In the case of stellar clusters the synthetic photometry is obtained from the average SED of population synthesis models. In these cases, and in addition to the success of the $10\times LLL$ test, the χ^2 minimization procedure is valid as far as (a) the synthetic photometry used has an intrinsic variance due to size of sample effects much lower than the uncertainty in the data (Cerviño & Luridiana 2006), (b) size of sample effects do not produce biased synthetic photometry (Cerviño & Valls-Gabaud 2003),

and (c) the average values obtained from the models and used in the fit are representative of the intrinsic underlying distribution, that is, the underlying distribution of integrated luminosity have a gaussian-like shape and the intrinsic variance can be translated to gaussian-like confidence intervals and χ^2 minimization procedures are valid (Cerviño & Luridiana 2006)¹¹; this last requirement implies the analysis of high-order moments of the distribution and a first order estimation of the mass and age of the cluster in absence of external constraints and once the $10\times LLL$ requirement is fulfilled by the observational data. Although, from the LLL test, we know that the results from CHORIZOS should be interpreted with caution for the individual clusters analyzed (but valid for the cluster as a whole), we have used it to obtain a first order estimation of the effects of extinction and reddening which would modify the LLL test.

The first step of the program is to read the unreddened SED models, extinguish them according to a given extinction law, and obtain the synthetic photometry. To run the program, CHORIZOS requires a file with the photometry data and a series of input parameters, such as the model family, understood as the collection of SED from stellar atmosphere models or synthetic stellar populations, and the range of the parameters to be used. Then, CHORIZOS reads the model photometry from the tables calculated previously, interpolates, calculates the likelihood for each grid point, and writes the results for each of the four parameters.

In the case of our study, we have used the STARBURST99 models (Leitherer et al. 1999) with the implementation by Smith et al. (2002) which includes a grid of blanketed stellar atmospheres at different metallicities. We fixed two parameters: the known metallicity of NGC 5471 and the type of dust, leaving unconstrained the amount of extinction and the age.

Regarding extinction, CHORIZOS works with $E(4405-5495)$ and R_{5495} , which are the monochromatic equivalent to $E(B-V)$ and R_V respectively, the values 4405 and 5495 referring to the central wavelength (in Å) of the B and V filters. We used the standard type of dust characterized by a value $R_{5495} = 3.1$. The metallicity of the region was assumed to be traced by the oxygen abundance. Recent derivations from detailed spectrophotometric studies give a mean value of $12+\log(O/H)$ of 8.06 ± 0.03 for components A, C and D; a slightly lower abundance of 7.94 ± 0.03 is found for component B (Kennicutt, Bresolin & Garnett 2003). These values correspond to about 0.25 the solar oxygen abundance, if the value by Asplund et al. (2005) for the solar oxygen abundance is assumed. Therefore we used the value $Z = 0.2Z_\odot$ in CHORIZOS.

4. DISCUSSION

In this section we discuss the results of the photometry in terms of the resolved stellar photometry in the CMD and in terms of the integrated properties, both of the individual clusters defined in section 3.2 and of the whole star forming complex. We attempt to bring all the results into a coherent picture of the past and present star formation processes in NGC 5471.

¹¹ This requirement is actually linked with the $10\times LLL$ and the unbiased photometry requirement.

⁹ The latest version can be obtained from <http://www.iaa.es/~jmaiz>

¹⁰ Synthesis models provide an average SED with a relative variance equal to zero only in the case of clusters with an infinite number of stars (Cerviño & Luridiana (2006)).

4.1. Cluster Analysis

Analysing the integrated properties of a complex region like NGC 5471 is an exercise that has to be undertaken with care, because the integrated photometry includes a wide range of regions with different cluster masses, ages and extinction values. Thus the result of synthesizing the integrated ultraviolet-to-NIR photometry with CHORIZOS, which finds the most likely single stellar population (SSP) under unconstrained inputs for mass, age and extinction, is only of general interest as a guiding signpost. If we use only the optical-to-NIR photometry, CHORIZOS finds a most likely SSP with relatively high extinction and a young age 3 ± 2 Myr. If we include the FUV and NUV GALEX photometry then CHORIZOS finds two loci of maximum likelihood for a single SSP, one that corresponds to an age of 8 ± 2 Myr with moderate extinction and a second maximum at an age 60 ± 15 Myr and very low extinction. This result suggests that a significant fraction of the GALEX flux integrated within the 15 arcsec radius aperture from NGC 5471 is produced by a post-nebular stellar population of B stars (see also Waller et al. 1997).

Three previous studies have modelled the age of NGC 5471 using ultraviolet-to-optical spectra. Rosa & Benvenuti (1994) use an HST/FOS spectrum through an aperture of 4.3 arcsec around knot A. Mas-Hesse & Kunth (1999) use an IUE spectrum through an aperture of 10×20 arcsec and the FOS optical spectrum of Rosa & Benvenuti (1994). Pellerin (2006) uses a FUSE spectrum through an aperture of 4×20 arcsec. All three works find that the UV spectrum of NGC 5471 can be explained with a young burst of less than about 5 Myr and a relatively low extinction. These results are consistent with the detection of Wolf-Rayet (WR) stars in NGC 5471 (Mas-Hesse & Kunth 1999). However these previous works may not be sensitive to an older population since they are based on the analysis of UV continuum and absorption lines (Si IV and C IV) and optical emission lines as primary age indicators, and are thus biased towards younger knots with brightest ultraviolet fluxes; while the integrated GALEX photometry through a large aperture is more sensitive to the extended, fainter, more evolved stellar population¹². Indeed, Meurer et al. (1995), Maoz et al. (1996), and Chandar et al. (2005) have found that the relative contribution from the cluster stellar population to the total UV flux in starbursts is only a fraction in the range $\sim 20\%$ to $\sim 40\%$, the majority of the UV flux coming from a diffuse fainter stellar population that is most prominent when the total flux is integrated, just as in the case of NGC 5471. In addition, the analysis performed with CHORIZOS focus the results on the continuum shape. This discrepancy between ages inferred from emission lines and from the continuum points towards a complex star formation history in NGC 5471 as we show below.

The integrated photometry analysis of the clusters identified in section 3.2 may be affected by size of sample effects due to the failure of the $10 \times \text{LLL}$ test in some of the clusters. However, we present here the analysis to show, as a case of study, the possible interpretations. The values quoted must not be taken, in any case, as

¹² Recall that the 1σ detection for the GALEX data is $AB_{\text{FUV}}=27.6$ mag arcsec⁻²




FIG. 9.— $H\alpha$ and J-V versus J-H plot for the clusters identified in section 3.2 (V stands for the 547M filter). A clear correlation of decreasing $H\alpha$ with redder colors points to an aging effect within the ongoing starburst phase.

final values for cluster ages.

Figure 9 shows a color-color- $H\alpha$ plot of the individual clusters. The supernova knot is not shown, and knots 3 and 4 have been combined into a single knot 34¹³. There is a clear correlation in the sense that redder knots have less $H\alpha$ flux. The flux of $H\alpha$ can decrease due to the aging of the burst or to different clusters having different masses, less massive bursts producing fewer ionizing photons¹⁴. This latter could be the case, including a relationship with color, when strong size of sample effects are present and just a few stars are responsible for most of both the $H\alpha$ and continuum emission (over-luminous case) or by the absence of the most massive stars which mimics variations in the upper mass limit of the Initial Mass Function (under-luminous case; e.g. Villaverde et al. 2010).

Knot 1 is the brightest in $H\alpha$ and the age estimations obtained by CHORIZOS give the youngest age, 3 ± 2 Myr, with the lowest extinction. For knots 2, 3, 4, 7, 8, 9, 10 CHORIZOS estimates an intermediate age, 5 ± 2 Myr, with an intermediate extinction, except may be knot 9 which has some indications for a somewhat higher extinction. Knots 5 and 11 have older age estimations, 9 ± 3 Myr. However, except for Knot 1, 2 and 34, the age estimations can also be explained by size-of-sample effects with under-luminous case. In these cases, age estimations, although apparently consistent, should not be considered as final, pending a more complete analysis with additional data sets.

¹³ The nature of knots 3+4 is not clear, it may be that both are part of the same cluster that has evolved sufficiently for the stellar winds to evacuate its center from ionized gas. Further higher spatial resolution IR and UV imaging is needed to establish more details.

¹⁴ Extinction may also play a small role but values significantly larger than reported in the literature, which are lower than $E(B-V)=0.14$, would be required.

In summary, from the cluster analysis of individual bright knots and from the integrated photometry of the whole complex there are clear indications that there is a complex star formation in NGC 5471 event, with indications of an older population of B stars and a luminous young ionizing cluster. This will be well established with the analysis of the CMD in the next section.

4.1.1. Mass of the ionized gas

The H^+ mass and the mass of the ionizing cluster may be derived from the $H\alpha$ flux. The published values of internal extinction for NGC 5471 differ from different authors, but they are lower than about $E(B-V)=0.14$ on average (Skillman 1985; Torres-Peimbert et al. 1989; Kennicutt & Garnett 1996; Luridiana et al. 2002; Esteban et al. 2002). In NGC 604 Maíz Apellániz et al. (2004) have estimated that only about 10% of the $H\alpha$ flux is missing in the higher opacity zones. Therefore, we have not attempted to correct the measured $H\alpha$ flux to estimate other magnitudes from this value. The electron density assumed is $n_e = 100 \text{ cm}^{-3}$ (Luridiana et al. 2002).

The $H\alpha$ flux in a $15''$ radius circular aperture (uncorrected for internal extinction) yields a lower limit to the luminosity $L_{H\alpha} \sim 2.3 \times 10^{40} \text{ erg s}^{-1}$. The total number of H-ionizing photons, $Q(H^0)$, estimated from Osterbrock (1989) is:

$$Q(H^0) = \frac{\alpha_B}{\alpha_{H\alpha}^{eff}} \times \frac{L_{H\alpha}}{h\nu_{H\alpha}} \sim 2.2 \times 10^{52} \text{ s}^{-1}$$

where $\alpha_B/\alpha_{H\alpha}^{eff} \sim 2.99$, assuming case B recombination, $\alpha_B \sim 2.59 \times 10^{-13} \text{ cm}^{-3} \text{ s}^{-1}$, and an effective recombination coefficient for $H\alpha$ of $8.63 \times 10^{-14} \text{ cm}^{-3} \text{ s}^{-1}$ for 10^4 K and $n_e = 100 \text{ cm}^{-3}$ (Osterbrock 1989). Thus the total (lower limit) ionized mass of the gas cloud is

$$M_{H^+} = Q(H^0) \frac{m_p}{n_e \alpha_B} \sim 7.3 \times 10^5 M_\odot$$

From evolutionary models of single stellar population ionizing clusters and radiation-bounded H II regions, a relation between $Q(H^0)$ per solar mass and the $H\beta$ equivalent width can be found (Díaz 1998), which allows to estimate the stellar cluster mass by taking into account the cluster evolution:

$$\log[Q(H^0)/M_\odot] = 0.86 \log[EW(H\beta)] + 44.48 \quad (5)$$

Hence, a lower limit for the mass of the cluster can be estimated by means of the $H\beta$ equivalent width and the $H\alpha$ luminosity of the region. Using the range of values $EW(H\beta)=134-296 \text{ \AA}$ published by different authors (Luridiana et al. 2002; Esteban et al. 2002; Rosa & Benvenuti 1994; Rosa 1981), and the value of $Q(H^0)$ calculated above, equation 5 yields a mass of the ionizing stellar cluster in the range $0.6 - 1.1 \times 10^6 M_\odot$. Using the calibration of Kennicutt (1998) and the luminosity that we measure, $L_{H\alpha} \sim 2.3 \times 10^{40} \text{ erg s}^{-1}$, we obtain a star formation rate of $0.18 M_\odot \text{ yr}^{-1}$, or $2.1 \times 10^{-7} M_\odot \text{ yr}^{-1} \text{ pc}^{-2}$ (taking the area of the region as the circular aperture defined in Figure 4), that translates into a cluster mass of $10^6 M_\odot$ for a burst duration of 10 Myr, which is the mean duration of the current burst implied by the analysis in the previous section. Nevertheless, it

is known that this calibration was computed for a particular star formation episode at nearly constant rate during more than 100 Myr, so it might be not suitable for bursty systems. We have applied the new calibration by Oti-Floranes & Mas-Hesse (2010)¹⁵, which makes a distinction between instantaneous (IB) and extended burst (EB). We used as input our measured $H\alpha$ luminosity, no color excess, and a Salpeter Initial Mass Function in the range $1-100 M_\odot$. For the case of instantaneous burst, Oti-Floranes & Mas-Hesse (2010) use the concept of star formation strength (SFS), defined as the total mass of gas transformed into stars during the burst, giving three different ages for the IB case. We obtained a SFS of $1.5 \times 10^6 M_\odot$ for a burst of 4 Myr, $2.3 \times 10^6 M_\odot$ for 5 Myr, and $1.0 \times 10^7 M_\odot$ for the 6 Myr case. For a EB, the results are given in terms of the standard star formation rate (SFR), with three different tabulated ages, namely: 10, 30 and 250 Myr. However, in this age range the results are independent of the age for the $H\alpha$ estimator. If the region would be experiencing a continuous constant star formation, the SFR given by this calibration would be $0.1 M_\odot \text{ yr}^{-1}$, less than a factor of 2 lower than the calibration by Kennicutt (1998)¹⁶.

Thus we find that the masses of ionized gas and of the stellar cluster in the current star formation event are both of the same order of magnitude, close to $10^6 M_\odot$. This similarity may be understood in terms of a very high efficiency in star formation. Given that this is not the first event of star formation in NGC 5471 in the last 100 Myr, this high star formation efficiency takes an important meaning that implies that there has to be a large reservoir of gas to maintain this important star formation activity.

Although optical images show NGC 5471 apparently isolated in the outskirts of M101, the H I distribution of M101 shows that NGC 5471 is, in fact, one of the brightest regions in H I, located in a spiral arm (cf. figure 1). The thermal radio continuum emission from NGC 5471 has the highest observed central emission measure of all the M101 complexes. Closely coincident with this H II radio continuum peak, there is an H I concentration of nearly $10^8 M_\odot$ (Viallefond et al. 1981). The general distribution of the H I gas in M101 follows that of the diffuse FUV emission, with enhancements in the 21 cm line emission seen near FUV peaks. Smith et al. (2000) include NGC 5471 as one of their 35 photodissociation regions (PDRs) candidates. Their Ultraviolet Imaging Telescope (UIT) FUV flux measurement is in good agreement with our GALEX measurement of $9.8 \times 10^{-14} \text{ erg cm}^{-2} \text{ s}^{-1} \text{ \AA}^{-1}$, and NGC 5471 is clearly the brightest FUV peak in the whole M101 galaxy. This is reflected in a decreased molecular content surrounding NGC 5471 which has been dissociated by the high star formation efficiency, the highest in M101 as calculated by Giannakopoulou-Creighton et al. (1999).

4.2. CMD

¹⁵ Their web tool can be found at <http://www.laeff.cab.inta-csic.es/research/sfr/>

¹⁶ This calibration integrates a Salpeter IMF in the mass range $0.1-100 M_\odot$, which predicts a larger mass.




FIG. 10.— Final CMD with isochrones divided into five age bins, drawn by their concave hull, and shown with different colours. Error bars correspond to an average error in each magnitude bin. The right hand side of the figure shows the luminosity function. The line across the bottom shows the completeness limit at the 50% level in the core (dashed line) and in the rest of the image (solid line).

The photometry of the individual stars presented in the color-magnitude diagram, $m_{547M} - m_{675W'}$ (V-R) vs. m_{547M} (V), of figure 10 is a powerful tool to further understand the star formation history in NGC 5471. The isochrones represented in the figure have been divided into five age bins, (4-10, 10-25, 25-50, 50-75, 75-100) Myr, and drawn by their concave hull, shown with different colours. The right hand side of the figure shows the luminosity function, which peaks at $M_{547M} = 24$, and becomes incomplete for fainter stars, as indicated by the 50% completeness limit shown. We recall that this CMD is the result of a careful process of calibration, measurement and cleaning, as detailed in section 3.1 above. We have not included in the CMD those point-like sources with a partially resolved PSF, that are likely to be compact clusters. At the distance of M101 some of the point sources are unresolved multiple systems, some of which may have been included in the CMD, but these will not really affect any of the arguments that we present here.

A glance at the CMD tell us at once that star formation has been proceeding more or less continuously for the last 100 Myr. The diagram is populated by stars of $\sim 4 - 50 M_{\odot}$. We can readily identify clear structures in the diagram. A well-defined main-sequence at V-R ~ -0.1 , which begins with the brightest star at 19 mag (that corresponds to an age of ~ 4 Myr) and goes all the

way down to 25 mag. Red stars span a range of 3 – 4 magnitudes in brightness, indicating that star formation has occurred during the last $\sim 15 - 70$ Myr. There are some traces of the blue-plume at $M_V = -9$, indicating ongoing star formation. A strip of stars following a patch from $[0.6, 25]$ to $[1.1, 22.5]$ form the red giant branch.

4.2.1. Mass in stars and star formation history

In order to quantify the relative importance of the present burst to the star formation history during the previous 100 Myr in NGC 5471, we make a rough estimate of the stellar mass from the CMD. We follow three different approaches. One method consists in assigning a mass to each of the stars in the CMD, corresponding to the most probable isochrone. This is done considering a 2D Gaussian probability density distribution centered on the distance in the color-magnitude space of a given observed star to the isochrones with dispersions being the estimated errors for the photometry. Once a mass has been assigned to a star, we count the stars in the mass range $6-55 M_{\odot}$ and integrate a Salpeter IMF in the mass range $1-100 M_{\odot}$. The result of this calculation gives $\sim 2 \times 10^5 M_{\odot}$. The second method is as follows: first we assign a mean stellar mass of $6 M_{\odot}$ to the stars in the most populated bin of the luminosity function, $m_{547M} = 23.5$. This mass is then scaled up by the ratio




FIG. 11.— STARFISH recovered Star Formation History of NGC 5471.

of the total m_{547M} of NGC 5471 to the magnitude of the bin $m_{547M} = 23.5$. The resulting mass is used to normalize the IMF at the bin corresponding to $6 M_{\odot}$. The result of integrating a Salpeter IMF in the range 1-100 M_{\odot} thus normalized gives a value of $\sim 5 \times 10^5 M_{\odot}$.

A third independent method to estimate the mass is based on the fit of the CMD by means of Hess diagrams. We have used the code STARFISH¹⁷ (Harris & Zaritsky 2001, 2002), with the latest patchsets, to find a best fit to the CMD by a linear combination of Hess diagrams at different ages. We have used our own set of isochrones described in section 3.1.3. The best-fit SFH of NGC 5471 is shown in Figure 11. Figure 12 shows the synthetic CMD of NGC 5471 constructed using the SFH amplitudes output of the best-fit SFH; the observed CMD is also shown for reference. The synthetic main sequence seems tighter and bluer compared to the observed one, probably due to differential reddening and underestimated errors. The SFH derived seems to be consistent with a continuous one, but the errors only allow to take into consideration two episodes: a dominant young burst < 20 Myr, preceded by a longer event during the period 20-100 Myr. According to the SFR, the integrated mass in stars of the youngest event is comparable to the oldest one, with $\sim 10^6 M_{\odot}$.

Although these methods give only an order of magnitude estimate, we can conclude that the integrated mass of stars formed in the past 20-100 Myr is of the order of magnitude of the current star formation event, that we have calculated above as $\sim 10^6 M_{\odot}$. If the star formation proceeds in an isolated gas cloud, we would expect that the rate at which stars form would decrease with time, as less gas is left available to form new stars. This is what is observed in many giant HII regions with two or more generations of star formation, where the latest event is less massive than the previous. In the case of NGC 5471 the results from the integrated photometry and from the CMD indicate that the current star forming event is as massive as those during the previous 20-100 Myr. We can




FIG. 12.— NGC 5471 synthetic CMD based on the best-fit SFH solution of STARFISH (left) and the observed one (right).

understand this in the context of the large H I spiral arm in which the region is immersed (cf. section 4.1.1). In this respect, Waller et al. (1997) conclude from a morphological study of M101 that NGC 5471 may be the result of tidal interactions of M101 with the nearby galaxies NGC 5477 and NGC 5474 in the time interval 100-1000 Myr ago.

4.2.2. Spatial distribution of the star formation history

Given the long duration of the star formation in NGC 5471, ~ 100 Myr, and its large size ~ 1 kpc, it is natural to question the spatial location of the star formation through time along the extent of the region. In order to visualize this, we have selected four different areas in the CMD and proceeded to locate spatially the stars in these four boxes. Figure 13 displays the resulting distributions. The youngest and more massive stars (top-left panel) are clearly concentrated in the main star forming emission line knots, implying that massive stars are now forming mainly in clusters. Only two stars are not directly associated with these knots, one of which belongs to an isochrone of 20 Myr. The bottom-right panel displays the distribution of intermediate mass stars ($\sim 5-10 M_{\odot}$) older than about 50 Myr; these stars are distributed mainly towards the halo, with only a few in the core of the region. The top-right and bottom-left panels show the distribution of intermediate mass stars ($\sim 10-15 M_{\odot}$), both those which are in the main sequence and those which have already evolved out of it. The distributions of stars in these two CMD boxes are clearly concentrated fairly uniformly throughout the core of NGC 5471; some of the stars in these two boxes are found in the halo, with a sparse distribution somewhat similar to the older lower mass stars in the bottom-right panel. Because the stars in these two intermediate boxes are of the same mass but they are found in a range of evolutionary stages, this implies that star formation has proceeded more or less uniformly in the core for the last $\sim 20-50$ Myr.

From this analysis of the spatial distribution of the CMD, a clear picture emerges in which the star formation in the complex NGC 5471 has proceeded in a general spatio-temporal sequence from the periphery to the core. During the first epoch, $\sim 50-100$ Myr ago, the star formation occurred along the periphery and the core, then a second major event $\sim 10-20$ Myr ago was more or less uniformly distributed mainly in the core, and finally the current ionizing star forming event is mostly concen-

¹⁷ Available at <http://www.noao.edu/staff/jharris/SFH/>




FIG. 13.— Spatial distribution of the star formation with time. The CMD contains only stars with magnitudes below the 50% completeness defined in the core region. The spatial distribution of the stars within four boxes selected in the CMD are shown in the right hand side images. The images are also drawn with a circle of 15 arcsec radius, indicating the area of the integrated photometry, an ellipse delineating the core region where the present star forming event occurs, and the polygons selected for the cluster analysis. The square points represent the stars in the box selected in the CMD, the light color points indicate the stars located in the core of the region (inner ellipse), while the black points stand for the stars belonging to the halo. Notice how the younger stars are concentrated in the inner clusters (top-left panel) and intermediate and older stars populate uniformly the region.

trated in the singular bright clusters located inside the core, where the gas reservoir is presumably higher¹⁸. At the same time, we have seen from both the integrated photometry analysis and the CMD, that as the events proceeded concentrating from the periphery to the core clusters, the amount of mass of gas formed into stars seems to be of the same order of magnitude, but more concentrated in time, with higher star formation rate.

We note that the current event of ionizing clusters is apparently contained within a large bubble which defines the core of NGC 5471. This bubble, of projected size 400×550 pc, is clearly defined geometrically (cf. figure 2) and kinematically (Muñoz-Tuñón et al. 1995), and is likely to have been produced by the stars that formed ~ 20 Myr ago.¹⁹

There are other examples that seem to follow the general process of star formation that we have outlined here for NGC 5471. Úbeda et al. (2007) find an inwards sequence of star formation and a bubble for cluster I-A in NGC 4214. Walborn & Blades (1997) find a triggered spatio-temporal distribution of stars in 30 Doradus, but this sequence occurs at the scale of the individual clusters in NGC 5471. Indeed there are indications that at

this smaller scale, ~ 50 pc, the evolution of the different individual clusters indicated by the age dating is also reflected in their morphology (e.g. as mentioned in the case of 3+4), but a detailed study at these scales requires the high resolution UV-optical-IR imaging that can only be provided by the WF3 camera onboard HST.

5. CONCLUSIONS

We have performed a photometric study of NGC 5471, a GEHR in the outskirts of the spiral galaxy M101, to derive its star formation history by means of resolved stellar photometry and integrated cluster photometry. Furthermore, integrated photometry integrated photometry of the whole region, using data from GALEX (ultraviolet), HST/WFPC2 (optical), and TNG (near infrared), yields two possible solutions for a single stellar population: one that corresponds to an age of ~ 8 Myr with moderate extinction and one with an age around 60 Myr and very low extinction. This degeneration is typical of this kind of approach when spatially integrated data are used and reflects the complexity of GEHR which include clusters with different ages and extinction values.

From the photometric analysis of the eleven clusters defined on the IR H image a correlation emerges in the sense that redder knots have less $H\alpha$ flux, showing a clear aging trend. The ages range from 3 Myr for the youngest cluster, up to 10 Myr for the oldest one. However, the Lowest Luminosity Limit test prevents us from taking these estimates at face value, since only a few individual

¹⁸ Notice that the age dating results from the individual cluster photometry is compatible with this age-spatial distribution of the younger stars in the CMD, and this reinforces the age results obtained for the clusters.

¹⁹ The results from a kinematical analysis of the expansion of this bubble are in progress and will be published elsewhere

clusters satisfy the required limit.

The complex history of star formation of NGC 5471 revealed by the cluster analysis is confirmed by the resolved stellar analysis. From the CMD it is clear that star formation has been proceeding continuously with more or less intensity for the last 100 Myr. The well-defined main-sequence gives a youngest age of about 4 Myr, while red stars, which span a range of 3-4 magnitudes, indicate that star formation has occurred during the last 15-70 Myr.

We have found that the masses of the ionized gas and of the stellar cluster in the current star formation event are both of the same order of magnitude, around $10^6 M_{\odot}$, which may be understood in terms of a very high efficiency. In fact, the star formation strength of NGC 5471 is more than a factor of 2 that of NGC 604 in M33 (Relaño & Kennicutt 2009). This implies that there has to be a large reservoir of gas to maintain this star formation rate, something that is confirmed by the huge HI concentration in which the region is located.

From the spatial distribution of the stars, we can conclude that the star formation in NGC 5471 has proceeded in a general spatio-temporal sequence which was more extended in the past and now is concentrated in clusters in the core. The current event of ionizing clusters is contained within a large bubble, which is likely to have been produced by the stars that formed ~ 20 Myr ago. This leads to the general question of whether a low density

“seed” generation of evolved intermediate mass stars is in fact a prerequisite to trigger a starburst event (Brandner 2002). More UV-optical-IR data at higher spatial resolution, such as that can be provided by the WF3 camera on board HST, are obviously needed in order to have a conclusive answer.

We have benefited from comments and suggestions by Emilio Alfaro, David Martínez Delgado, and Nolan Walborn. This work has been funded by DGICYT programs AYA2004-02703, AYA2007-64712, AYA2004-08260-C03-03, and AYA2007-67965-C03-03. RGB acknowledges support from the Spanish MEC through FPI grant BES-2005-6910 and from the China National Postdoc Fund Grant No. 20100480144. This work has made use of data from the archives of NASA/ESA Hubble Space Telescope, obtained at the Space Telescope Science Institute, which is operated by the Association of Universities for Research in Astronomy, Inc., under NASA contract NAS5-26555, and of data from the Telescopio Nazionale Galileo, operated on the island of La Palma by the Galileo Galilei Foundation INAF in the Spanish Observatorio del Roque de Los Muchachos of the Instituto de Astrofísica de Canarias. Thanks to cheerful Francesca Ghinassi for her help during the TNG observations. We thank an anonymous referee for very useful comments that improved the presentation of the paper.

REFERENCES

- Anderson, J., & King, I. R. 1999, *PASP*, 111, 1095
Aparicio, A., & Gallart, C. 1995, *AJ*, 110, 2105
Asplund, M., Grevesse, N., Sauval, A. J. 2005, *Cosmic Abundances as Records of Stellar Evolution and Nucleosynthesis*, 336, 25
Bellazzini, M., Ferraro, F. R., & Buonoanno, R. 1999, *MNRAS*, 307, 619
Bertelli, G., Bressan, A., Chiosi, C., Fagotto, F., and Nasi, E. 1994, *A&AS*, 106, 275
Bianchi, L., et al. 2005, *ApJ*, 619, L71
Brandner, W. 2002, *Modes of Star Formation and the Origin of Field Populations*, 285, 105
Braun, R. 1995, *A&AS*, 114, 409
Cardelli, J. A., Clayton, G. C. & Mathis, J. S. 1989, *ApJ*, 345, 245
Cerviño, M., & Valls-Gabaud, D. 2003, *MNRAS*, 338, 481
Cerviño, M., & Luridiana, V. 2004, *A&A*, 413, 145
Cerviño, M., & Luridiana, V. 2006, *A&A*, 451, 475
Chandar, R., Leitherer, C., Tremonti, C. A., Calzetti, D., Aloisi, A., Meurer, G. R., & de Mello, D. 2005, *ApJ*, 628, 210
Chen, C.-H. R., Chu, Y.-H., Gruendl, R., Lai, S.-P., & Wang, Q. D. 2002, *AJ*, 123, 2462
Díaz, A. I., 1999, *Ap&SS*, 263, 143
Dolphin, A. E. 2000, *PASP*, 112, 1383
Dolphin, A. E. 2000, *PASP*, 112, 1397
Esteban, C., Peimbert, M., Torres-Peimbert, S., & Rodríguez, M. 2002, *ApJ*, 581, 241
Giannakopoulou-Creighton, J., Fich, M., & Wilson, C. D. 1999, *ApJ*, 522, 238
Girardi, L. and Bertelli, G. 1998, *MNRAS*, 300, 533
Girardi, L., Bertelli, G., Bressan, A., Chiosi, C., Groenewegen, M. A. T., Marigo, P., Salasnich, B., and Weiss, A. 2002, *A&A*, 391, 195
Girardi, L., Bressan, A., Bertelli, G., and Chiosi, C. 2000, *A&AS*, 141, 371
Harris, J., & Zaritsky, D. 2001, *ApJS*, 136, 25
Harris, J., & Zaritsky, D. 2002, *Observed HR Diagrams and Stellar Evolution*, 274, 600
Heyer, Biretta, et al. 2004, *WFPC2 Instrument Handbook*, Version 9.0 (Baltimore: STScI)
Holtzman, J., et al. 1995, *PASP*, 107, 156
Jenkins, L. P., Roberts, T. P., Warwick, R. S., Kilgard, R. E., & Ward, M. J. 2004, *MNRAS*, 349, 404
Kennicutt Jr., R. C. 1998, *ApJ*, 498, 541
Kennicutt Jr., R. C., Bresolin, F., Garnett, D. R. 2003, *ApJ*, 591, 801
Kennicutt, R. C., Jr., & Garnett, D. R. 1996, *ApJ*, 456, 504
Krist, J. 1995, *ASP Conf. Ser. 77: Astronomical Data Analysis Software and Systems IV*, ed. R. A. Shaw, H. E. Payne & J. J. E. Hayes (San Francisco: ASP), 349
Leitherer, C., Schaerer, D., Goldader, J. D., González-Delgado, Rosa M., Robert, C., Kune, D. F., de Mello, D. F., Devost, D., Heckman, T. M. 1999, *ApJS*, 123, 3
Luridiana, V., Esteban, C., Peimbert, M., & Peimbert, A. 2002, *Revista Mexicana de Astronomía y Astrofísica*, 38, 97
Luridiana, V., Pérez, E., & Cerviño, M. 2003, *AJ*, 125, 3196
Maíz Apellániz, J. 2001, *ApJ*, 563, 151
Maíz Apellániz, J., Pérez, E., & Mas-Hesse, J. M. 2004, *AJ*, 128, 1196
Maíz Apellániz, J. 2004, *PASP*, 116, 859
Maíz Apellániz, J. 2007, *The Future of Photometric, Spectrophotometric and Polarimetric Standardization*, 364, 227
Maoz, D., Barth, A. J., Sternberg, A., Filippenko, A. V., Ho, L. C., Macchetto, F. D., Rix, H.-W., & Schneider, D. P. 1996, *AJ*, 111, 2248
Martin, D. C., et al. 2005, *ApJ*, 619, L1
Mas-Hesse, J. M., & Kunth, D. 1999, *A&A*, 349, 765
Meurer, G. R., Heckman, T. M., Leitherer, C., Kinney, A., Robert, C., & Garnett, D. R. 1995, *AJ*, 110, 2665
Mighell, K. J., Rich, R. M., Shara, M., & Fall, S. M. 1996, *AJ*, 111, 2314
Morrissey, P., et al. 2005, *ApJ*, 619, L7
Muñoz-Tuñón, C., Gavryusev, V., & Castañeda, H.O. 2005, *AJ*, 110, 1630
Oti-Flóranes, H., & Mas-Hesse, J. M. 2010, *A&A*, 511, A61
Osterbrock, D., 1989, *Astrophysics of Gaseous Nebulae and Active Galactic Nuclei* (Mill Valley: University Science Book)
Pellerin, A. 2006, *AJ*, 131, 849
Relaño, M., & Kennicutt, R. C. 2009, *ApJ*, 699, 1125
Rosa, M. R., & Benvenuti, P. 1994, *A&A*, 291, 1
Rosa, M. 1981, Ph.D. Thesis

- Schlegel, D. J., Finkbeiner, D. P., & Davis, M. 1998, *ApJ*, 500, 525
- Shaklan, S. Sharman, M. C., & Pravdo, S. H. 1995, *Appl. Opt.*, 34, 6672
- Skillman, E. D. 1985, *ApJ*, 290, 449
- Smith, D. A., Allen, R. J., Bohlin, R. C., Nicholson, N., & Stecher, T. P. 2000, *ApJ*, 538, 608
- Smith, L. J., Norris, R. P. F., & Crowther, P. A. 2002, *MNRAS*, 337, 1309
- Stetson, P. B., et al. 1998, *ApJ*, 508, 491
- Stetson, P. B., & Harris, W. E. 1988, *AJ*, 96, 909
- Torres-Peimbert, S., Peimbert, M., & Fierro, J. 1989, *ApJ*, 345, 186
- Úbeda, L., Maíz Apellániz, J., & MacKenty, J. W. 2007, *AJ*, 133, 932
- Villaverde, M., Cerviño, M., & Luridiana, V. 2010, *A&A*, 522, A49
- Viallefond, F., Allen, R. J., & Goss, W. M. 1981, *A&A*, 104, 127
- Walborn, N. R., & Blades, J. C. 1997, *ApJS*, 112, 457
- Walborn, N. R., Barbá, R. H., Brandner, W., Rubio, M., Grebel, E. K., & Probst, R. G. 1999, *AJ*, 117, 225
- Waller, W. H., et al. 1997, *ApJ*, 481, 169
- Westera, P., Lejeune, T., Buser, R., Cuisinier, F., and Bruzual, G. 2002, *A&A* 381, 524 <ftp://ftp.astro.unibas.ch/pub/westera>